

令和 08 年度				調査			
北新保地内ポンプ更新工事（実施）				設計書		設計	
工事番号				施工地			
				村上市 北新保 地内			
		実施・元		変更			
設計額		7,095,000 円		円			
契約額 (内消費税額)		円 (円)		円 (円)			
工事・履行日数		工事日数 日間 又は 完成期限 年 月 日		日間(付与日数 日間) 完成期限 年 月 日			
実施 (元) 設計概要	ポンプ更新 N=2箇所			変更 設計概要			

消費税総括表

(単位：円)

項目	実 施		変 更 (1 回 目)			変 更 (2 回 目)		
	設 計	請 負	設 計	請 負		設 計	請 負	
				合 計	増 減 分		合 計	増 減 分
工 事 価 格	(1)	(4)	(7)	(10)= (7)*(6)/(3)	(13)= (10)-(4)	(16)	(19)= (16)*(6)/(3)	(22)= (19)-(10)
工 事 価 格 計	6,450,000							
本 工 事 費								
附 帯 工 事 費								
補 償 工 事 費								
消費税 相当額	(2)=(1)*0.10	(5)=(4)*0.10	(8)=(7)*0.10	(11)= (10)*0.10	(14)= (11)-(5)	(17)= (16)*0.10	(20)= (19)*0.10	(23)= (22)*0.10
消費税相当額計	645,000							
本 工 事 費								
附 帯 工 事 費								
補 償 工 事 費								
工 事 費	(3)=(1)+(2)	(6)=(4)+(5)	(9)=(7)+(8)	(12)= (10)+(11)	(15)= (13)+(14)	(18)= (16)+(17)	(21)= (19)+(20)	(24)= (22)+(23)
工 事 費 計	7,095,000							
本 工 事 費								
附 帯 工 事 費								
補 償 工 事 費								

工事費内訳表

費目・工種・施工名称など	数	量	単 位	金 額	備 考
ポンプ（製作）					
製作工事原価					
			式	2,831,000	
用排水機製作工					
			式	2,831,000	
機器単体費					
			式	2,831,000	
機器単体費					
			式	2,831,000	
04 機器単体費					
			式	2,831,000	
深井戸用水中ポンプ PM80×4-57.5 ケーブル30m 地上部付 三相200V 50Hz 見積 04 機器単体費					
	2		台		
直接工事費（製作）					
				2,831,000	
直接製作費					
					2,831,000
工事価格					
				2,830,000	

工事費内訳表

費目・工種・施工名称など			数	量	単	位	金	額	備	考
ポンプ（据付）										
直接工事費(仮設工を除く)										
						式		1,759,000		
用排水機据付工										
						式		1,759,000		
用排水機据付工										
						式		1,759,000		
用排水機据付工										
						式		1,759,000		
用排水機据付工										
						式		1,759,000		
0 省略		揚水管 溶融亜鉛メッキ 80A×2.75m 見積								
			16			本				
0 省略		揚水管用ボルト・ナット・パッキン SUS M12 見積								
			18			面分				
0 省略		電極棒 ケーブル30m付 見積								
			4			本				
0 省略		消耗品雑材 見積								
			1			式				

工事費内訳表

費目・工種・施工名称など					数	量	単	位	金	額	備	考
		0	省略	施工費（ポンプ及び揚水管更新）								
				PM80×4-57.5								
				見積 ※積算数量は各項目に記載								
					2			箇所				
		0	省略	運搬機械（機械据付共）								
				トラック（クレーン装置付）2 t 車								
				見積 ※数量2日で積算								
								日				
直接工事費（据付）												
										1,759,000		
共通仮設費（率分）												
										456,000		
共通仮設費計												
										456,000		
純工事費												
										2,215,000		
現場管理費（率分）												
										548,000		
現場管理費計												
										548,000		
据付間接費												
										0		

工事費内訳表

頁0-0004

費目・工種・施工名称など					数	量	単	位	金	額	備	考
間接工事費												
									1,004,000			
据付工事原価												
									2,763,000			
工事原価												
									5,594,000			
一般管理費等												
									854,000			
契約保証費												
									2,000			
一般管理費等												
									856,000			

工事費内訳表

頁0-0005

費目・工種・施工名称など				数	量	単	位	金	額	備	考
工事価格計											
								6,450,000			
消費税相当額計											
								645,000			
工事費計											
								7,095,000			